



माखनलाल चतुर्वेदी राष्ट्रीय पत्रकारिता एवं संचार विश्वविद्यालय

(मध्य प्रदेश विधानसभा के अधिनियम क्रमांक १५, १९९० द्वारा स्थापित)

MAKHANLAL CHATURVEDI NATIONAL UNIVERSITY OF JOURNALISM & COMMUNICATION
(Setup by Act No. 15, 1990 of M.P. Legislative Assembly)

क्रमांक....५१२.../सं.शा./2026

भोपाल, दिनांक: ...१३/03/2026

प्रति,

.....
.....
.....

विषय:- विश्वविद्यालय बिसनखेड़ी परिसर के बाँयज हॉस्टल के सामने क्रिकेट विकेट विस्तार किये जाने हेतु दरें आमंत्रित करने के संबंध में।

उपरोक्त विषयान्तर्गत विश्वविद्यालय बिसनखेड़ी परिसर के विज्ञापन बाँयज हॉस्टल के सामने क्रिकेट विकेट विस्तार किये जाने हेतु संलग्न विवरण अनुसार दरें आमंत्रित की जाती हैं।

अतः पत्र जारी होने के दिनांक से 7 दिवस के अंदर कार्य स्थल का निरीक्षण कर संलग्न प्रारूप अनुसार बंद लिफाफे में अपनी दरें "कुलसचिव, माखनलाल चतुर्वेदी राष्ट्रीय पत्रकारिता एवं संचार विश्वविद्यालय भोपाल" के नाम पर संधारण शाखा में जमा करें।

(प्रो. पी. शशिकला)

प्रभारी कुलसचिव

भोपाल, दिनांक: ...१३.../03/2026

क्रमांक....५१३.../सं.शा./2026

प्रतिलिपि

- 1) निज सहायक कुलगुरु एवं कुलसचिव की ओर सूचनार्थ।
- 2) विश्वविद्यालय के सूचना पटल पर चस्पा किये जाने हेतु।
- 3) विश्वविद्यालय के वेबसाईट पर जारी किये जाने हेतु।

(प्रो. पी. शशिकला)

प्रभारी कुलसचिव

FINANCIAL BID

Name Of Work : Extension & Construction Of Cricket Pitch At Boys Hostel Bisankhedi Campus At Bisankhedi Campus BHOPAL (M.P)

I/We hereby bid for the execution of the above work within the time specified at the rate (in figures) _____ (in words) _____ percent below/ above or at par based on the Bill of Quantities based on MP PWD SOR for Building & Internal W/S & S/F & Internal Electrification work w.e.f. 01.01.2024 & CG PWD SOR for Road w.e.f. 01/07/2022 with upto-date amendments in SOR. 01.01.2024 till issued date of NIT and item wise rates given therein in all respects and in accordance with the specifications, designs, drawings and instructions in writing in all respects in accordance with such conditions so far as applicable. I/We have visited the site of work and am/ are fully aware of all the difficulties and conditions likely to affect carrying out the work. I/We have fully acquainted myself/ourselves about the conditions in regard to accessibility of site and quarries/kilns, nature and the extent of ground, working conditions including stacking of materials, installation of tools and plant conditions effecting accommodation and movement of labor etc. required for the satisfactory execution of contract.

Should this bid be accepted, I/We hereby agree to abide by and fulfill all the terms and provisions of the said conditions of contract annexed hereto so far as applicable, or in default thereof to forfeit and pay to the Governor of Madhya Pradesh or his successors in office the sums of money mentioned in the said conditions.

Note:

- i. *Only one rate of percentage above or below or at par based on the Bill of Quantities and item wise rates given therein shall be quoted.*
- ii. *Percentage shall be quoted in figures as well as in words. If any difference in figures and words is found lower of the two shall be taken as valid and correct rate. If the bidder is not ready to accept such valid and correct rate and declines to furnish performance security and sign the agreement his earnest money deposit shall be forfeited.*
- iii. *In case the percentage "above" or "below" is not given by a bidder, his bid shall be treated as nonresponsive.*
- iv. *All duties, taxes, and other levies payable by the bidder shall be included in the percentage quoted by the bidder.*
- v. *Except GST all duties, taxes of Central and State Government, Local Bodies and authorities & Other levies payable by the bidder shall be deemed to be included in the rate quoted by the bidder.*

Signature of Bidder:

Name of Bidder :

The above bid is hereby accepted by me on behalf of the Governor of Madhya Pradesh dated the _____ day of _____ 2026.

REGISTRAR (I/C)
MCNUJC UNIVERSITY, Bhopal (M.P.)
(Signature of Officer by whom accepted)

Chanlal Chaturvedi National University Of Journalism and Communication, Bhopal(M.P.)

Detailed Estimate for Cricket Pitch at Boys Hostel Bisankhedhi Campus.

(as per MPPWD SOR 2024/ 01.01.2024 & CG PWD SOR FOR 01/07/2022)

S.No	SOR Item	Particular	Quantity	Unit	Rate	Amount
1	2.6	Excavation soil: Earth work in excavation by mechanical means (Hydraulic excavator) / manual means over areas (exceeding 30cm in depth. 1.5m in width as well as 10 sqm on plan) including dressing of sides and ramming of bottom disposal of excavated earth, lead up to 50m and lift up to 1.5m, disposed earth to be levelled and neatly dressed. (No extra lift is payable if work is done by mechanical means) All kinds of soil	35.75	CUM	147	5,255.25
2.	2.27.1	Under floor filling : Supplying and filling in plinth under floors including watering ramming consolidating in layers not exceeding 20cm in depth and dressing complete. Hard muram hard copra :With hard muram having CBR >12 % at under floors including watering, ramming and compacting (minimum compaction 95% of MDD) in layers not exceeding 20cm in thickness and dressing complete. (Note:- maximum thickness of this layer to be provided shall be 30cm)	9.90	CUM	393	3,893.06
3	CG PWD SOR FOR 01/07/2022 IRC;4.01 A .(ii)	Granular Sub-base with Close Graded Material (Table:- 400-1) Plant Mix Method with Mechanically crushed stone only(Construction of granular sub-base by providing close graded Material, mixing in a mechanical mix plant at OMC, carriage of mixed Material to work site, spreading in uniform layers with motor grader on prepared surface and compacting with vibratory power roller to achieve the desired density, complete as per clause 401: for Grading- II Material	9.90	CUM	1663	16,463.70
3.	2.26	Under floor filling stone dust: Supplying and filling in plinth with crusher stone dust / coarse sand under floors including, watering, ramming and compacting in layers not exceeding 20cm in depth and dressing complete Note: - Maximum thickness of this layer shall be 20 cm.	9.90	CUM	672	6,652.80
4.	5.2.1	RCC in walls, columns, pillars etc : Reinforced cement concrete work (with 20 mm nominal size graded stone aggregate) in walls (any thickness), including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, posts and struts etc. above plinth level and upto floor two level excluding cost of centring, shuttering, finishing and reinforcement: M-20 Grade Concrete	8.225	cum	6231	51,249.98

4.24.1.1		PCC with RMC (using PPC Cement): Providing and laying in position ready mixed plain cement concrete, with cement content as per approved design mix and manufactured in fully automatic batching plant and transported to site of work in transit mixer for all leads, having continuous agitated mixer, manufactured as per mix design of specified grade for plain cement concrete work, including pumping of R.M.C. from transit mixer to site of laying and curing, excluding the cost of centering, shuttering and finishing, including cost of curing, admixtures in recommended proportions as per IS : 9103 to accelerate/ retard setting of concrete, improve workability without impairing strength and durability as per direction of the Engineer-in-charge. M-20: M-20 grade plain cement concrete (cement content considered @ 280kg/cum)	3.25	CUM	5910	19,207.50
6	11.36	Kota stone flooring: Kota stone slab flooring over 20 mm (average) thick base laid over and jointed with grey cement slurry mixed with pigment to match the shade of the slab including rubbing and mirror polishing complete with base of cement mortar 1 : 4 (1 cement : 4 sand) having thickness of slab 25 mm (Area of slab to be over 0.25 sqm) Note: - Deduction shall be made for not mirror polishing according to item no 11.43 *SOR No11.43 Mirror polishing on marble work/Granite work/stone work wherever required to give high gloss finish complete. (164 rs to be deducted)	65	SQM	1174 - 164 = 1010	65,650.00
				Total		1,68,372.29
				Say		1,68,372 Rs./-
(One Lakh Sixty Eight Thousand Three Hundred Seventy Two Rupees)						